BRUHAT BANGALORE MAHANAGARA PALIKE

BILL OF QUANTITIES (BOQ)

Name of Work: Providing Basic facilities for Ganesha Immersion at Ganesha temple kalyani Sahakaranagara in Kodigehalli ward no. 8.

Sl. No.	Approved Qty.	Description	Unit	Issued to Technical Manager , KRIDL	
				In Figures	In Words
1	1	Supply of Drinking Water through water tankers of Capacity 5000 Liters.Hiring of Water Tanker	per day	242.80	Rupees Two Hundred Forty Two and Eighty Paise Only
2	1	Hire Charges of Tractor 40 HP including Operator and Fuel	per day	1520.00	Rupees One Thousand Five Hundred Twenty Only
3	5	Procurement of Water	Per Load	108.00	Rupees One Hundred Eight Only
4	1	Engaging Heavy Mazdoor	per day	259.88	Rupees Two Hundred Fifty Nine and Eighty Eight Paise Only
5	90	Engaging Heavy Mazdoor 10x9	per day	513.00	Rupees Five Hundred Thirteen Only
6	7.50	Providing Stone dust to approach road and near immersion tank for levelling and to protect not to sliping Sl No. 50 Code 400 metal Component PWD SR Page No II SR 2016-17	Cum	800.00	Rupees Eight Hundred Only
7	66.00	Hire charge of pumping water 3.5 KL/hr capacity Pump Page No. XXXXVI / Sl NO. 49 PWD SR 2016-17 Pumping of Waste Water From Emersion Tank	Hrs	50.00	Rupees Fifty Only
8	100.00	Providing Causal Labours (Unskilled mazdoor Heavy) (PWD SR 2016-17 Page No. LIV / I. 5)	Days	258.88	Rupees Two Hundred Fifty Eight and Eighty Eight Paise Only
9	720.00	Providing erecting removing casurinapole barricading using poles of 7.50 to 10 cms, dia and 1.5 height above ground fixed vertically at intervals of 2.0 to 2.5 mtrs. C/C an horizontally at 0.50 mtr, above ground level, including fixing poles in the ground level for minimum depth of 3.0 mtr and tied with coir rope firmly including cost and conveyance of all materials, labour, lead and lift charges and complete on hire basis as per the engineer in charge. (Approved Rate) Vertical Poles,Horizontal Poles	Mtrs	65.00	Rupees Sixty Five Only
10	15000.0	Hire Charge for Shamiyana with Necessary Bambo Poles, Erection Charges Including transportation - (Size: 40ft x 40ft = 1600 sqft) (Approved Rate)	Sft	8.00	Rupees Eight Only
11	165.00	Hire Charges for Shamiyana Side Wall of 8ft Hight (Size: 10x 15ft = 150 Rft) (Approved Rate)	Rft	17.00	Rupees Seventeen Only
12	220.00	Hire Charge for Armless Plastic Chairs (Approved Rate)	Nos	4.00	Rupees Four Only
13	180.00	Hire Charge for Wooden Table of Size 6ft x 2ft (Approved Rate)	Nos	40.00	Rupees Forty Only
14	1320.00	Hire Charge for supplying and running circuit service main with necessary messanger wire and reel insulators and maintaining the same 4 of 25 sqmm PVC insulated and sheathedaluminium wire (KPWD SR 2010-11 P.55/I.6 III b)	Mtrs	9.00	Rupees Nine Only
15	60.00	1321 Hire charge of 100 KVA Generator including operator, Fuel, transportation and Handling charges (PWD SR 2016-17 (P.XXXXVII / I.92)	Hrs	630.00	Rupees Six Hundred Thirty Only
16	110.00	Hire chargesfor Flood lighting arrangements for the stage and existing immersion Tank during night time (Approved Rate)	Nos	285.00	Rupees Two Hundred Eighty Five Only

1. The work should be executed as per the specification and standard specified by the PWD & Other specifications of the Bangalore
2. The work should be carried out as per the directions and instructions of the concerned Engineer
3. The Contractor should maintain the quality of work as per the standard specifications.

30/08

Executive Engineer (Byatarayanapura)
Bruhath Bangalore Mahanagara Palike

I am prepared to take up the above work at the rates quoted by me in the Schedule 'B'. 30/08

EXECUTIVE ENGINEER-4
KRIDL BBMP DIVISION
BENGALURU-560 010

Signature of the contractor

Executive Engineer